#### Deutsches Institut für Bautechnik

### Zulassungsstelle für Bauprodukte und Bauarten

### **Bautechnisches Prüfamt**

Eine vom Bund und den Ländern gemeinsam getragene Anstalt des öffentlichen Rechts

Kolonnenstraße 30 B D-10829 Berlin Tel.: +49 30 78730-0 Fax: +493078730-320 E-Mail: dibt@dibt.de

www.dibt.de





Mitglied der EOTA Member of EOTA

# **European Technical Approval ETA-11/0216**

English translation prepared by DIBt - Original version in German language

Handelsbezeichnung Trade name

Zulassungsinhaber Holder of approval

Zulassungsgegenstand und Verwendungszweck

Generic type and use of construction product

Geltungsdauer:

vom Validity: from

bis to

Herstellwerk Manufacturing plant fischer Injektionssystem FIS EM cc fischer Injection system FIS EM cc

fischerwerke GmbH & Co. KG Otto-Hahn-Straße 15 79211 Denzlingen

DEUTSCHLAND

Verbunddübel in den Größen Ø 8 mm bis Ø 40 mm zur Verankerung im Beton

Bonded anchor in the size of Ø 8 mm to Ø 40 mm for use in concrete

10 June 2011

16 February 2015

fischerwerke

Diese Zulassung umfasst This Approval contains

26 Seiten einschließlich 17 Anhänge 26 pages including 17 annexes





Page 2 of 26 | 10 June 2011

### I LEGAL BASES AND GENERAL CONDITIONS

- 1 This European technical approval is issued by Deutsches Institut für Bautechnik in accordance with:
  - Council Directive 89/106/EEC of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products<sup>1</sup>, modified by Council Directive 93/68/EEC<sup>2</sup> and Regulation (EC) N° 1882/2003 of the European Parliament and of the Council<sup>3</sup>;
  - Gesetz über das In-Verkehr-Bringen von und den freien Warenverkehr mit Bauprodukten zur Umsetzung der Richtlinie 89/106/EWG des Rates vom 21. Dezember 1988 zur Angleichung der Rechts- und Verwaltungsvorschriften der Mitgliedstaaten über Bauprodukte und anderer Rechtsakte der Europäischen Gemeinschaften (Bauproduktengesetz - BauPG) vom 28. April 1998<sup>4</sup>, as amended by law of 31 October 2006<sup>5</sup>;
  - Common Procedural Rules for Requesting, Preparing and the Granting of European technical approvals set out in the Annex to Commission Decision 94/23/EC<sup>6</sup>;
  - Guideline for European technical approval of "Metal anchors for use in concrete Part 5: Bonded anchors", ETAG 001-05.
- Deutsches Institut für Bautechnik is authorized to check whether the provisions of this European technical approval are met. Checking may take place in the manufacturing plant. Nevertheless, the responsibility for the conformity of the products to the European technical approval and for their fitness for the intended use remains with the holder of the European technical approval.
- This European technical approval is not to be transferred to manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those indicated on page 1 of this European technical approval.
- This European technical approval may be withdrawn by Deutsches Institut für Bautechnik, in particular pursuant to information by the Commission according to Article 5(1) of Council Directive 89/106/EEC.
- Reproduction of this European technical approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of Deutsches Institut für Bautechnik. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European technical approval.
- The European technical approval is issued by the approval body in its official language. This version corresponds fully to the version circulated within EOTA. Translations into other languages have to be designated as such.
- Official Journal of the European Communities L 40, 11 February 1989, p. 12
- <sup>2</sup> Official Journal of the European Communities L 220, 30 August 1993, p. 1
- Official Journal of the European Union L 284, 31 October 2003, p. 25
- Bundesgesetzblatt Teil I 1998, p. 812
- 5 Bundesgesetzblatt Teil I 2006, p. 2407, 2416
- Official Journal of the European Communities L 17, 20 January 1994, p. 34



Page 3 of 26 | 10 June 2011

### II SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

## 1 Definition of product and intended use

### 1.1 Definition of the construction product

The fischer injection system FIS EM cc is a bonded anchor consisting of a cartridge with injection mortar fischer FIS EM cc and a steel element. The steel elements are either

- fischer anchor rods in the range of M8 to M30 or
- fischer internal threaded anchor RG MI in the range of M8 to M20 or
- Reinforcing bar in the range of Ø 8 to Ø 40 or
- fischer rebar anchor FRA in the range of 12 to 24.

The steel element is placed into a drilled hole filled with injection mortar and is anchored via the bond between metal part, injection mortar and concrete.

An illustration of the product and intended use is given in Annexes 1 and 2.

### 1.2 Intended use

The anchor is intended to be used for anchorages for which requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 of Council Directive 89/106 EEC shall be fulfilled and failure of anchorages made with these products would cause risk to human life and/or lead to considerable economic consequences. Safety in case of fire (Essential Requirement 2) is not covered in this European technical approval. The anchor is to be used only for anchorages subject to static or quasi-static loading in reinforced or unreinforced normal weight concrete of strength classes C20/25 at minimum and C50/60 at most according to EN 206:2000-12.

The anchor may be used in cracked or non-cracked concrete.

The anchor may be installed in dry or wet concrete.

The anchor may be used in the following temperature ranges:

Temperature range I: -40 °C to +60 °C (max long term temperature +35 °C and

max short term temperature +60 °C)

Temperature range II: -40 °C to +72 °C (max long term temperature +50 °C and max short term temperature +72 °C)

### Elements made of zinc coated steel:

The element made of zinc plated or hot dipped galvanised steel may only be used in structures subject to dry internal conditions.

## Elements made of stainless steel:

The element made of stainless steel may be used in structures subject to dry internal conditions and also in structures subject to external atmospheric exposure (including industrial and marine environment), or exposure to permanently damp internal conditions, if no particular aggressive conditions exist. Such particular aggressive conditions are e.g. permanent, alternating immersion in seawater or the splash zone of seawater, chloride atmosphere of indoor swimming pools or atmosphere with extreme chemical pollution (e.g. in desulphurization plants or road tunnels where de-icing materials are used).



Page 4 of 26 | 10 June 2011

### Elements made of high corrosion resistant steel:

The element made of high corrosion resistant steel may be used in structures subject to dry internal conditions and also in structures subject to external atmospheric exposure, in permanently damp internal conditions or in other particular aggressive conditions. Such particular aggressive conditions are e. g. permanent, alternating immersion in seawater or the splash zone of seawater, chloride atmosphere of indoor swimming pools or atmosphere with chemical pollution (e.g. in desulphurization plants or road tunnels where de-icing materials are used).

## Elements made of reinforcing bars:

Post-installed reinforcing bars may be used as anchor designed in accordance with the EOTA Technical Report TR 029 only. Such applications are e.g. concrete overlay or shear dowel connections or the connections of a wall predominantly loaded by shear and compression forces with the foundation, where the reinforcing bars act as dowels to take up shear forces. Connections with post-installed reinforcing bars in concrete structures designed in accordance with EN1992-1-1: 2004 are not covered by this European technical approval.

The provisions made in this European technical approval are based on an assumed working life of the anchor of 50 years. The indications given on the working life cannot be interpreted as a guarantee given by the producer, but are to be regarded only as a means for choosing the right products in relation to the expected economically reasonable working life of the works.

## 2 Characteristics of the product and methods of verification

### 2.1 Characteristics of the product

The anchor corresponds to the drawings and provisions given in Annexes 1 to 7. The characteristic material values, dimensions and tolerances of the anchor not indicated in Annex 1 to 7 shall correspond to the respective values laid down in the technical documentation of this European technical approval.

The characteristic values for the design of anchorages are given in Annexes 10 to 17.

The two components of the injection mortar fischer FIS EM cc are delivered in unmixed condition in side-by side-cartridges of sizes 390 ml, 585 ml or 1100 ml according to Annex 1. Each cartridge is marked with the imprint "fischer FIS EM cc", with processing notes, shelf life, curing time, processing time (depending on temperature), hazard code.

Each fischer anchor rod is marked with the identifying mark of the producer and property class in accordance with Annex 3.

Each fischer internal threaded anchor RG MI is marked with the marking of steel grade and length in accordance with Annex 4. Each fischer internal threaded anchor RG MI made of stainless steel is marked with the additional letter "A4". Each fischer internal threaded anchor RG MI made of high corrosion resistant steel is marked with the additional letter "C".

Each fischer rebar anchor FRA is marked with the identifying mark of the producer and the trade name according to Annex 7.

Elements made of reinforcing bars shall comply with the specifications given in Annex 6.

The marking of embedment depth may be done on jobsite.

The technical documentation of this European technical approval is deposited at the Deutsches Institut für Bautechnik and, as far as relevant for the tasks of the approved bodies involved in the attestation of conformity procedure, is handed over to the approved bodies.



Page 5 of 26 | 10 June 2011

### 2.2 Methods of verification

The assessment of fitness of the anchor for the intended use in relation to the requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 has been made in accordance with the "Guideline for European technical approval of Metal Anchors for Use in Concrete", Part 1 "Anchors in general" and Part 5 "Bonded anchors", on the basis of Option 1.

In addition to the specific clauses relating to dangerous substances contained in this European technical approval, there may be other requirements applicable to the products falling within its scope (e.g. transposed European legislation and national laws, regulations and administrative provisions). In order to meet the provisions of the Construction Products Directive, these requirements need also to be complied with, when and where they apply.

### 3 Evaluation and attestation of conformity and CE marking

### 3.1 System of attestation of conformity

According to the Decision 96/582/EG of the European Commission<sup>8</sup> system 2(i) (referred to as System 1) of the attestation of conformity applies.

This system of attestation of conformity is defined as follows:

System 1: Certification of the conformity of the product by an approved certification body on the basis of:

- (a) Tasks for the manufacturer:
  - (1) factory production control:
  - (2) further testing of samples taken at the factory by the manufacturer in accordance with a prescribed control plan;
- (b) Tasks for the approved body:
  - (3) initial type-testing of the product;
  - (4) initial inspection of factory and of factory production control:
  - (5) continuous surveillance, assessment and approval of factory production control.

Note: Approved bodies are also referred to as "notified bodies".

### 3.2 Responsibilities

### 3.2.1 Tasks for the manufacturer

### 3.2.1.1 Factory production control

The manufacturer shall exercise permanent internal control of production. All the elements, requirements and provisions adopted by the manufacturer shall be documented in a systematic manner in the form of written policies and procedures, including records of results performed. This production control system shall insure that the product is in conformity with this European technical approval.

The manufacturer may only use initial/raw/constituent materials stated in the technical documentation of this European technical approval.

Official Journal of the European Communities L 254 of 08.10.1996



### Page 6 of 26 | 10 June 2011

The factory production control shall be in accordance with the control plan which is part of the technical documentation of this European technical approval. The control plan is laid down in the context of the factory production control system operated by the manufacturer and deposited at Deutsches Institut für Bautechnik.<sup>9</sup>

The results of factory production control shall be recorded and evaluated in accordance with the provisions of the control plan.

### 3.2.1.2 Other tasks for the manufacturer

The manufacturer shall, on the basis of a contract, involve a body which is approved for the tasks referred to in section 3.1 in the field of anchors in order to undertake the actions laid down in section 3.2.2 For this purpose, the control plan referred to in sections 3.2.1.1 and 3.2.2 shall be handed over by the manufacturer to the approved body involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this European technical approval.

## 3.2.2 Tasks for the approved bodies

The approved body shall perform the

- initial type-testing of the product,
- initial inspection of factory and of factory production control,
- continuous surveillance, assessment and approval of factory production control

in accordance with the provisions laid down in the control plan.

The approved body shall retain the essential points of its actions referred to above and state the results obtained and conclusions drawn in a written report.

The approved certification body involved by the manufacturer shall issue an EC certificate of conformity of the product stating the conformity with the provisions of this European technical approval.

In cases where the provisions of the European technical approval and its control plan are no longer fulfilled the certification body shall withdraw the certificate of conformity and inform Deutsches Institut für Bautechnik without delay.

### 3.3 CE marking

The CE marking shall be affixed on each packaging of the anchor. The letters "CE" shall be followed by the identification number of the approved certification body, where relevant, and be accompanied by the following additional information:

- the name and address of the producer (legal entity responsible for the manufacture),
- the last two digits of the year in which the CE marking was affixed,
- the number of the EC certificate of conformity for the product,
- the number of the European technical approval,
- the number of the guideline for European technical approval,
- use category (ETAG 001-1, Option 1),
- size.

The control plan is a confidential part of the European technical approval and only handed over to the approved body involved in the procedure of attestation of conformity. See section 3.2.2.



Page 7 of 26 | 10 June 2011

# 4 Assumptions under which the fitness of the product for the intended use was favourably assessed

### 4.1 Manufacturing

The European technical approval is issued for the product on the basis of agreed data/information, deposited at Deutsches Institut für Bautechnik, which identifies the product that has been assessed and judged. Changes to the product or production process, which could result in this deposited data/information being incorrect, should be notified to Deutsches Institut für Bautechnik before the changes are introduced. Deutsches Institut für Bautechnik will decide whether or not such changes affect the approval and consequently the validity of the CE marking on the basis of the approval and if so whether further assessment or alterations to the approval shall be necessary.

## 4.2 Design of anchorages

The fitness of the anchor for the intended use is given under the following conditions:

The anchorages are designed in accordance with the EOTA Technical Report TR 029 "Design of bonded anchors" under the responsibility of an engineer experienced in anchorages and concrete work.

Post-installed reinforcing bars may be used as anchor designed in accordance with the EOTA Technical Report TR 029 only. The basic assumptions for the design according to anchor theory shall be observed. This includes the consideration of tension and shear loads and the corresponding failure modes as well as the assumption that the base material (concrete structural element) remains essentially in the serviceability limit state (either non-cracked or cracked) when the connection is loaded to failure. Such applications are e.g. concrete overlay or shear dowel connections or the connections of a wall predominantly loaded by shear and compression forces with the foundation, where the reinforcing bars act as dowels to take up shear forces. Connections with reinforcing bars in concrete structures designed in accordance with EN 1992-1-1:2004 (e.g. connection of a wall loaded with tension forces in one layer of the reinforcement with the foundation) are not covered by this European technical approval.

Fischer Anchor rods may be replaced by commercial standard threaded rods, washers and hexagon nuts made of galvanised steel or stainless steel if the following requirements are fulfilled:

- material, dimensions and mechanical properties of the metal parts according to the specifications given in Annex 5, Table 3,
- confirmation of material and mechanical properties of the metal parts by inspection certificate 3.1 according to EN 10204:2004, the documents should be stored,
- marking of the threaded rod with the envisage embedment depth. This may be done by the manufacturer of the rod or the person on jobsite.

For the fischer internal threaded anchor RG MI fastening screws or threaded rods made of appropriate steel and strength class acc. to Annex 5 shall be specified. The minimum and maximum thread engagement length  $l_{\rm E}$  of the fastening screw or the threaded rod for installation of the fixture shall be met the requirements according to Annex 4, Table 2. The length of the fastening screw or the threaded rod shall be determined depending on thickness of fixture, admissible tolerances, available thread length and minimum and maximum thread engagement length  $l_{\rm E}$ .

Verifiable calculation notes and drawings are prepared taking account of the loads to be anchored.

Z21793.11 8.06.01-114/11

10

The Technoial Report TR 029 "Design of bonded anchors" is published in English on EOTA website <a href="www.eota.eu">www.eota.eu</a>.



### Page 8 of 26 | 10 June 2011

The position of the anchor is indicated on the design drawings (e.g. position of the anchor relative to reinforcement or to supports, etc.).

### 4.3 Installation of anchors

The fitness for use of the anchor can only be assumed if the anchor is installed as follows:

- anchor installation carried out by appropriately qualified personnel and under the supervision
  of the person responsible for technical matters of the site,
- anchor installation in accordance with the manufacturer's specifications and drawings using the tools indicated in the technical documentation of this European technical approval,
- use of the anchor only as supplied by the manufacturer without exchanging the components,
- reinforcing bars shall comply with specifications given in Annex 6,
- checks before placing the anchor to ensure that the strength class of the concrete in which the anchor is to be placed is in the range given and is not lower than that of the concrete to which the characteristic loads apply,
- check of concrete being well compacted, e.g. without significant voids,
- marking and keeping the effective anchorage depth,
- edge distance and spacing not less than the specified values without minus tolerances,
- positioning of the drill holes without damaging the reinforcement,
- drilling by hammer-drilling,
- in case of aborted drill hole: the drill hole shall be filled with mortar,
- cleaning the drill hole and installation in accordance with Annexes 8 and 9,
- during installation and curing of the chemical mortar the anchor component installation temperature shall be at least 5 °C,
- during curing of the chemical mortar the temperature of the concrete must not fall below +5 °C; observing the curing time according to Annex 5, Table 4 until the anchor may be loaded,
- for installation in bore holes h<sub>0</sub> > 150 mm extension hoses acc. Annex 1 shall be used,
- for overhead installation or in bore hole depth  $h_0 > 250$  mm injection-funnels acc. to Annex 1 shall be used,
- Fastening screw or threaded rods (including nut and washer) must comply with the appropriate material and strength class of the fischer internal threaded anchor RG MI,
- installation torque moments are not required for functioning of the anchor. However, the torque moments given in Annex 3 to 7 must not be exceeded.

### 5 Indications to the manufacturer

## 5.1 Responsibility of the manufacturer

The manufacturer is responsible to ensure that the information on the specific conditions according to 1 and 2 including Annexes referred to as well as sections 4.2 and 4.3 is given to those who are concerned. This information may be made by reproduction of the respective parts of the European technical approval.

In addition all installation data shall be shown clearly on the package and/or on an enclosed instruction sheet, preferably using illustration(s).



### Page 9 of 26 | 10 June 2011

The minimum data required are:

- drill bit diameter.
- diameter of anchor rod,
- information on the installation procedure, including cleaning of the hole with the cleaning equipments, preferably by means of an illustration,
- anchor component installation temperature,
- ambient temperature of the concrete during installation of the anchor,
- admissible processing time (open time) of the mortar.
- curing time until the anchor may be loaded as a function of the ambient temperature in the concrete during installation,
- identification of the manufacturing batch,

All data shall be presented in a clear and explicit form.


### 5.2 Packaging, transport and storage

The cartridges shall be protected against sun radiation and shall be stored according to the manufacturer's installation instructions in dry condition at temperatures of at least +5 °C to not more than +30 °C.

Cartridges with expired shelf life must no longer be used.

The anchor shall only be packaged and supplied as a complete unit. Cartridges may be packed separately from metal parts.

Georg Feistel Head of Department *beglaubigt:*Baderschneider



Page 11 of the European technical approval ETA-11/0216, issued on 10 June 2011





Table 1: Installation parameters fischer anchor rods

Size of ancho	r		[-]	M8	M10	M12	M14	M16	M20	M22	M24	M27	M30
Nominal drill b	oit diameter	d <sub>o</sub>	[mm]	12	14	14	16	18	24	25	28	30	35
Depth of drill h	nole	h <sub>o</sub>	[mm]					h <sub>o</sub> =	= h <sub>ef</sub>				
Effective anch	orage	h <sub>ef,min</sub>	[mm]	60	60	70	75	80	90	93	96	108	120
depth		h <sub>ef,max</sub>	[mm]	160	200	240	280	320	400	440	480	540	600
Minimum space and minimum distance		nin C min	[mm]	40	45	55	60	65	85	95	105	120	140
Diameter of clearence	pre-position anchorage	ed d,	[mm]	9	12	14	16	18	22	24	26	30	33
hole in the fixure	in-place anchorage	d <sub>f</sub>	[mm]	14	16	16	18	20	26	28	30	33	40
Minimum thickness h <sub>min</sub>			[mm]	h	h <sub>ef</sub> + 30 (≥100) h <sub>ef</sub> + 2d <sub>o</sub>								
Maximum torque moment T <sub>inst.max</sub>		[Nm]	10 20 40 50 60 120 135 150 200 30							300			
Thisteness of fi	t <sub>fix.min</sub>		[mm]					C	)				
Thickness of fixure		[mm]					30	00					

## fischer anchor rod



## Markierung:


Property class 8.8 or high corrosion-resistant Steel C, property class 80: • Stainless steel A4, property class 50 and high corrosion-resistant Steel C, property class 50: • •


fischer injection system FIS EM cc	Annex 3
fischer anchor rod Installation parameters and dimensions	of European technical approval ETA-11/0216

Table 2: Installation parameters fischer internal threaded anchors RG MI

Size of anchor			M8	M10	M12	M16	M20
Diameter of anchor	d <sub>H</sub>	[mm]	12	16	18	22	28
Nominal drill bit diameter	d <sub>o</sub>	[mm]	14	18	20	24	32
Length of anchor	L <sub>H</sub>	[mm]	90	90	125	160	200
Effective anchorage depth $h_{\rm ef}$ and drill hole depth $h_{\rm o}$	$h_{ef} = h_0$	[mm]	90	90	125	160	200
Minimum spacing and edge distance	s <sub>min</sub> = c <sub>min</sub>	[mm]	55	65	75	95	125
Diameter of clearence hole in the fixure	d <sub>f</sub>	[mm]	9	12	14	18	22
Minimum thickness of concrete member	h <sub>min</sub>	[mm]	120	125	165	205	260
County in double	[E,min	[mm]	8	10	12	16	20
Screw-in depth	I <sub>E,max</sub>	[mm]	18	23	26	35	45
Maximum torque moment	T <sub>inst,max</sub>	[Nm]	10	20	40	80	120

## fischer Internal threaded anchor RG MI





Marking: anchor size

e.g.: M10

Stainless steel additional A4

e.g.: M10 A4

High corrosion-resistant steel additional C

e.g.: **M10** C

fischer injection system FIS EM cc	Annex 4
fischer Internal threaded anchors RG MI Installation parameters and dimensions	of European technical approval ETA-11/0216

FIS FM cc-03-11

Table 3: Materials: anchor rods, threaded rods, washers, hexagon nuts and screws

Designation	Materials									
	Steel, zinc plated	Stainless steel (A4)	high corrosion-resistant steel (C)							
Anchor rod	Property class 5.8 or 8.8; EN ISO 898-1 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised ≥ 45 µm, EN ISO 10684	Property class 50 or 70 EN ISO 3506, EN 10088 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362	Property class 50 or 80 EN ISO 3506, or f <sub>uk</sub> = 700 N/mm <sup>2</sup> f <sub>yk</sub> = 560 N/mm <sup>2</sup> EN 10088 1.4462; 1.4539; 1.4565; 1.4529; 1.4547							
Washer EN ISO 7089	zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised ≥ 45 µm, EN ISO 10684	EN 10088 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362	EN 10088 1.4462; 1.4539; 1.4565; 1.4529; 1.4547							
Hexagon nut according to EN 24032	Property class 5 or 8; EN 20898-2 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised ≥ 45 µm, EN ISO 10684	Property class 50 or 70 EN ISO 3506, EN 10088 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362	Property class 50,70 or 80 EN ISO 3506, EN 10088 1.4462; 1.4539; 1.4565; 1.4529; 1.4547							
Screw or threaded rods for internal- threaded anchors RG MI	Property class 5.8 or 8.8; EN ISO 898-1 zinc plated ≥ 5µm, EN ISO 4042 A2K or hot-dip galvanised ≥ 45 µm, EN ISO 10684	Property class 70 EN ISO 3506, EN 10088 1.4401; 1.4404; 1.4578; 1.4571; 1.4439; 1.4362	Property class 70 EN ISO 3506, EN 10088 1.4462; 1.4539; 1.4565; 1.4529; 1.4547							

Table 4: Maximum permissible processing times and minimum curing times


System temperature [°C]	Max. processing time [minutes]	Minimum curing time <sup>1)</sup> [hours]
+5 to +10	120	40
≥+10 to +20	30	18
≥+20 to +30	14	10
≥+30 to +40	7	5

<sup>&</sup>lt;sup>1)</sup> For wet concrete the curing time must be doubled.

-	fischer injection system FIS EM cc	Annex 5
M cc-03-1	Materials	of European technical approval
Doc: FIS EM	Processing times, curing times	ETA-11/0216

Table 5:	Insta	llatior	n par	ame	eters	rein	forci	ing k	oars										
Nominal bar size	ød	[mm]	8	10	12	14	16	18	20	22	24	25	26	28	30	32	34	36	40
Nominal drill bit diameter	d <sub>o</sub>	[mm]	12	14	16	18	20	25	25	30	30	30	35	35	40	40	40	45	55
Drill hole depth	h <sub>o</sub>	[mm]							,		h <sub>o</sub> = h	) <sub>ef</sub>							
Effective	h <sub>ef,min</sub>	[mm]	60	60	70	75	80	85	90	94	98	100	104	112	120	128	136	144	160
anchorage depth	h <sub>ef,max</sub>	[mm]	160	200	240	280	320	360	400	440	480	500	520	560	600	640	680	720	800
Minimum spacing	e c <sub>min</sub>	[mm]	40	45	55	60	65	75	85	95	105	110	120	130	140	160	170	180	200
Minimum thickness of concrete mer		[mm]		h <sub>ef</sub> +	30 100							h <sub>ef</sub>	+ 2d	0					





## Refer to EN 1992-1-1 Annex C, Table C.1 and C.2N, properties of reinforcement:

Produkt form	Non-zinc-plated bars and de-coiled rod				
Class		В	С		
Characteristic yield strength f	or f <sub>0,2k</sub> [MPa]	400 t	o 600		
Minimum value of $k = (f_t / f_{yk})$	)	≥ 1,08	≥ 1,15 < 1,35		
Characteristic strain at maxim	um force, ε <sub>uk</sub> [%]	≥ 5,0 ≥ 7,5			
Bendability		Bend / Rebend test			
Maximum deviation from nominal mass (individual bar) [%]	Nominal bar size [mm] ≤ 8 > 8	± 6,0 ± 4,5			
Bond: Minimum relative rib area, f <sub>R,min</sub> (determination according to EN 15630)	0,0 0,0				

## Rib height h:


0,05 • d ≤ h ≤ 0,07 • d d = nominal bar size The rib height h must be:

fischer injection system FIS EM cc	Annex 6
Reinforcing bars Installation parameters Materials	of European technical approval ETA-11/0216

Table 6: Installation parameters fischer rebar anchors FRA

Threaded diameter				M 12	M 16	M 20	M 24	
Nominal bar size		d	[mm]	12	16	20	25	
Nominal drill bit diar	neter	d <sub>o</sub>	[mm]	16	20	25	30	
Depth of drill hole (	h <sub>0</sub> = ( e.ges )	h <sub>o</sub>	[mm]		h <sub>ef</sub> -	+ 1		
Effective anchorage	donth	h <sub>ef,mim</sub>	[mm]	70	80	90	96	
Lifective anchorage	ucptii	h <sub>ef,max</sub>	[mm]	140	220	300	380	
Distance concrete surface to welded join			[mm]	100				
Minimum spacing ar minimum edge dista	= C <sub>min</sub>	[mm]	55	65	85	105		
	ore-positioned anchorage	ď	[mm]	14	18	22	26	
in the fixure	n-place anchorage	d <sub>f</sub>	[mm]	18	22	26	32	
Minimum thickness of concrete member	h <sub>min</sub>	[mm]	h <sub>o</sub> +2d <sub>o</sub>					
Maximum torque moment		T <sub>inst,max</sub>	[Nm]	40	60	120	150	
Thickness of fixure minimum maximum		t <sub>fix</sub>	[Nm]		Ę	5	-	
		t <sub>fix</sub>	[Nm]		30	00		

## fischer rebar anchor FRA




Head marking e.g.: FRA (for stainless steel); FRA C (for high corrosion-resistant steel)

-	fischer injection system FIS EM cc	Annex 7
Doc: FIS EM cc-03-1	fischer rebar anchor FRA Installation Parameters	of European technical approval ETA-11/0216

## Drilling and cleaning the hole


1



Drill the hole.

Drill hole diameter  $d_0$  and drill hole depth  $h_0$  see Tables 1, 2, 5 or 6.

2




Clean the drill hole.

Blow out the drill hole two times, using oil-free pressure air (P > 6 bar).




3



Brush the drill hole two times, using a steel brush. For deep holes use an extension.

	12	14	16	18	20	24	25	28	30	32	35	40	45	55
d <sub>b</sub> [mm]	13	16	2	0	21,5	26	27	30		40		42	47	58

4




Blow out the drill hole two times, using oil-free pressure air (P > 6 bar).




## Preparing the cartridge

5




Twist off the sealing cap.
(Cartridge ≤ 600 ml)



Cut off the cap. (Cartridge 1100 ml)

6



Twist on the static mixer. (the spiral in the statik mixer must be clearly visible)


7



**H** 

Place the cartridge into the applicator gun.

8





Press approx 10 cm of material out until the resin is evenly grey in colour. Don't use mortar that is not uniformly gray.

fischer injection system FIS EM cc

Installation instructions Part I

Annex 8


of European Technical Approval

ETA-11/0216

Doc: FIS EM cc-03-11

## Injection of the mortar


9



Fill approx. 2/3 of the drill hole with mortar. Allways begin from the surface of the hole and avoid bubbles.




For drill hole depth ≥ 150 mm use an extention hose.




For overhead installation, deep holes  $h_0 > 250$  mm or drill hole diameter  $d_0 \ge 40$  mm use an injection-adapter.

### Installation fischer anchor rods or internal threaded anchors RG MI

10






Only use clean and oil-free anchor elements. Mark the anchor for setting depth. Press the anchor rod or internal threaded anchor down to the bottom of the hole, turning it slightly while doing so. After inserting the anchor element, excess mortar must emerge from the mouth of the hole.



For overhead installation support the anchor-rod with wedges.




For in-place anchorage fill the annual clearence with mortar.

11




Wait for the specified curing time, t<sub>cure</sub> see **Table 4**.



Mounting the fixure.
T<sub>inst,max</sub> see **Table 1** or **2**.

# Installation reinforcing bars and fischer rebar anchors FRA

10



Only use clean and oil-free rebars. Mark the reinforcing bar for setting depth. Using a turning movement, push the reinforcement bar or the FRA vigorously into the filled hole up to the insertion depth marking.

11



Wait for the specified curing time, t<sub>cure</sub> see **Table 4**.

T<sub>inst,max</sub>

Mounting the fixure.
T<sub>inst,max</sub> see **Table 6**.

fischer injection system FIS EM cc

Installation instructions Part II

Annex 9

of European technical approval

ETA-11/0216

Doc: FIS EM cc\_03-11

				M 8	M 10	M 12	M 14	M 16	M 20	M 22	M 24	M 27	M 3
Steel fa													
			5.8 [kN]	19	29	43	58	79	123	152	177	230	28
Rks		class	8.8 [kN]	30	47	68	92	126	196	243	282	368	44
rist e N	stainless	Pro- perty	50 [kN]	_19	29	43	58	79	123	152	177	230	28
acte	steel A4	class	70 [kN]	26	41	59	81	110	172	212	247	322	39
Characteristic resistance N <sub>Rks</sub>	high corrosion-	Pro-	50 [kN]	19	29	43	58	79	123	152	177	230	28
0.5	resistant	perty class	70 <sup>4)</sup> [kN]	26	41	59	81	110	172	212	247	322	39
	steel C		80 [kN]	30	47	68	92	126	196	243	282	368	44
		Property	$\overline{}$					1,5	_				
≥		class						1,5	-				
afet	stainless	Pro- perty	50 [-]					2,8		<del></del>			
ials or Y	steel A4		70 [-]					1,8					
Partial safety factor Y <sub>Ms.N</sub> ¹)	high corrosion-	110	50 [-]					2,8					
	resistant	perty class						1,5					
	steel C		80 [-]					1,6	50				
-	ed pullout ar								-				
	r for calculat		d [mm]	8	10	12	14	16	20	22	24	27	30
-	eristic bond ature range		e in non-	cracke	a conc	rete C2	20/25					I	
(60°C/	35°C)	τ <sub>Rk,ucr</sub> [	N/mm²]	16	15	15	14	14	13	13	13	13	12
Tempera (72°C /	ature range II 50°C)	τ <sub>Rk,ucr</sub> [	N/mm²]	13	12	12	12	11	11	11	11	10	10
	eristic bond		e in crac	ked co	ncrete	C20/2	5						
(60°C/		τ <sub>Rk,cr</sub> [	N/mm²]					7,	,0				
Tempera (72°C/	ature range II 50°C)	τ <sub>Rk,cr</sub> [	N/mm²]					6,	,0				
		_	/30 [-]					1,0	)2				
Im e == - '	m.a.		/37 [-]					1,0					
Increasi factors f	111		/45 [-] /50 [-]					1,0					
1001013	Rk		/50 [-] /55 [-]					1,0 1,0					
			/60 [-]					1,0					
Splitting	g failure												
		h /	h <sub>ef</sub> ≥ 2,0					1,0	h <sub>ef</sub>				
Edge dis		2,0 > h /	**					4,6 h <sub>ef</sub>	- 1,8 h				
		h /	h <sub>ef</sub> ≤ 1,3					2,26	h <sub>ef</sub>				
Spacing			sp [mm]					2c <sub>c</sub>	r,sp				
	afety factor				1,	5 <sup>2)</sup>				1,8			
	ence of other rtial safety fa						<sup>2)</sup> The pa <sup>4)</sup> f <sub>uk</sub> = 7	artial sa 700 <b>N</b> /I	afety fac mm²;	$f_{yk} = 5$	= 1,0 is 60 <b>N</b> /m	include nm²	d
<del>.</del>	fis	cher inje	ection sy	/stem	FIS EN	1 cc			Δ	nnex	( 10		
	£: a a la	er anch							o	f Euro	pean	roval	

Table	8: Charac	teristic v	alues to s	shear	load			hor ro					
Size				M8	M10	M12	M14	M16	M20	M22	M24	M27	M30
Steel fa	ilure without	lever arm											
, s		Property	5.8 [kN]	9	15	21	29	39	61	76	89	115	141
iti 🧏		class	8.8 [kN]	15	23	34	46	63	98	122	141	184	225
ce	stainless	Property	50 [kN]	9	15	21	29	39	61	76	89	115	141
Characteristic resistance V <sub>Rk,s</sub>	steel A4	class	70 [kN]	13	20	30	40	55	86	107	124	161	197
sist	high corrosion-	Proporty	50 [k <b>N</b> ]	9	15	21	29	39	61	76	89	115	141
5 5	resistant	Property class		13	20	30	40	55	86	107	124	161	197
	steel C		80 [kN]	15	23	34	46	63	98	122	141	184	225
Steel fai	ilure with lev	-						100					
RKS O.D.		Property	5.8[Nm]	19	37	65	104	166	324	447	560	833	1123
ğΣ		class Pro-	8.8 [Nm]	30	60	105	167	266	519	716	896	1333	1797
istic ieni	stainless steel A4	perty	50[Nm]	19	37	65	104	166	324	447	560	833	1123
om		<u> class</u>	70[Nm]	26	52	92	146	232	454	626	784	1167	1573
rac m	high corrosion-	Pro-	50[Nm]	19	37	65	104	166	324	447	560	833	1123
Characteristic bending moment M <sub>Rks</sub>	resistant steel C	perty class	70 <sup>3)</sup> [Nm] 80[Nm]	26 30	52 60	92 105	146 167	232 266	454 519	626 716	784 896	1167 1333	1573 1797
				30	00	105	107	200	519	/10	030	1333	1/3/
Partial S	afety factor							4.6	) F				
		Property class	5.8 [-] 8.8 [-]					1,2					
		Pro-		_				1,2					
γ <sub>Ms,V</sub> 1)	stainless steel A4	perty cl <b>ass</b>	5 <u>0 [-]</u> 70 [-]					2,3 1,5					
' Ms,V	high		50 [-]					2,3					
	corrosion-	Pro- perty						1,2					
	resistant steel C	class	80 [-]					1,3					
Concret	e pryout fail	ure	<u>00 [-]</u>					1,	<i>.</i>				
	in Equation (							_					
	al Report TR		k [-]					2,0	00				
Partial sa	Partial safety factor $\gamma_{Mcp}^{-1}$ [-]							1,	5 <sup>2)</sup>				
Concret	Concrete edge failure				Se	e Tech	nical R	eport T	R 029,	Section	5.2.3.	4	
5	afety factor		γ <sub>Mc</sub> 1) [-]					1	5 <sup>2)</sup>				

Table 9: Displacements of fischer anchor rods to tension load

Size		M 8	M 10	M 12	M 14	M 16	M 20	M 22	M 24	M 27	M 30
Non-cracked cond	rete and cracked con	crete;	tempe	rature	range	l to ll					
Displacement	$\delta_{NO}$ [mm/(N/mm <sup>2</sup> )]	0,07	0,08	0,09	0,09	0,10	0,11	0,11	0,12	0,12	0,13
Displacement	$\delta_{_{N\infty}}$ [mm/(N/mm <sup>2</sup> )]										

Calculation of characteristic displacement with  $\delta_{_{N}}$  = ( $\delta_{_{N0}}^{} \cdot \tau_{_{Sd}}^{})$  /1,4

Table 10: Displacements of fischer anchor rods to shear load

Size		M 8	M 10	M 12	M 14	M 16	M 20	M 22	M 24	M 27	M 30
Displacement	$\delta_{vo}$ [mm/kN]	0,18	0,15	0,12	0,10	0,09	0,07	0,07	0,06	0,05	0,05
Displacement	$\delta_{_{V\!\infty}}$ [mm/kN]										

Calculation of characteristic displacement with  $\delta_{\rm V}$  = ( $\delta_{\rm V0}$  •  $\rm V_{\rm Sd})$  /1,4

	fischer injection system FIS EM cc	Annex 11
Doc: FIS EM cc-04-11	fischer anchor rods Characteristic values to shear load	of European technical approval
Doc: FIS	Displacements	ETA-11/0216

<sup>&</sup>lt;sup>3)</sup>  $f_{uk} = 700 \text{ N/mm}^2$  ;  $f_{yk} = 560 \text{ N/mm}^2$ 

<sup>&</sup>lt;sup>1)</sup> In absence of other national regulations. <sup>2)</sup> The partial safety factor  $\gamma_2 = 1.0$  is included.

Table 11: Characteristic values to tension load fischer internal threaded anchors RG MI

Size				1	8 N	M 10	M 12	M 16	M 20
Steel failure									
Characteristic		Property	5.8 [kN		19	29	43	79	123
Characteristic resistance with	N	class	8.8 [kN	]	29	47	68	108	179
screw	$N_{Rk,s}$		A4 [kN	]	26	41	59	110	172
301044		class 70	C [kN	[]	26	41	59	110	172
		Property					1,50		
Partial safety	$\gamma_{Ms,N}^{ \  1\}}$	class					1,50		
factor	' IVIS,IN	Property					1,87		
		class 70	C [-	-]			1,87		
Combined pullout and conc	rete con					1			
Diameter for calculation			d <sub>H</sub> [mm		12	16	18	22	28
Effective anchorage depth			h <sub>ef</sub> [mm		90	90	125	160	200
Characteristic values in non	-cracked	concrete	C20/2	5					
Temperature range I (60°C /	35°C)4)	$N_{_{ m Rk}}$	<sub>ucr</sub> [kN	ן [ו	50	60	95	140	200
Temperature range II (72°C /	50°C) <sup>4)</sup>	N <sub>Rk</sub>	<sub>ucr</sub> [kN	j]	40	50	75	115	170
Characteristic values in crac	cked cor	crete C20	/25						
Temperature range 1 (60°C /	35°C)4)	N <sub>Rk</sub>	<sub>cr</sub> [kN	l] :	20	30	50	75	115
Temperature range II (72°C /	50°C)4)	N <sub>Rk</sub>	cr [kN	ıj :	20	25	40	60	95
		C2	5/30 [-	-]			1,02		
		<u>C3</u>	0/37 [-	-]			1,04		
Increasing factors for N <sub>Bk</sub>	$\Psi_{c}$	-	5/45 [-				1,06		
TRICE COLOR TO TAKE	- 0		0/50 [-	_			1,07		
			5/55 [				1,08		
		C5	0/60 [-	·]			1,09		
Splitting failure									
		h /	′ h <sub>ef</sub> ≥ 2,	0			1,0 h <sub>ef</sub>		
Edge distance c <sub>cr,sp</sub> [mm]		2,0 > h /	′ h <sub>ef</sub> > 1,	3			4,6 h <sub>ef</sub> - 1,	8 h	
		h /	′ h <sub>ef</sub> ≤ 1,	3			2,26 h	•	
Spacing		S <sub>cr,s</sub>	<sub>p</sub> [mm	]			2c <sub>cr,sp</sub>		
Partial safety factor γ <sub>Mp</sub> =	$\gamma_{Mc} = \gamma_{Ms}$	1) sp	[-	.]		1,5 <sup>2)</sup>			B <sup>3)</sup>

	fischer injection system FIS EM cc	Annex 12
00c: FIS EM cc-03-11	fischer Internal threaded anchors RG MI Characteristic values to tension load	of European technical approval ETA-11/0216

 $<sup>^{1)}</sup>$  In absence of other national regulations.  $^{2)}$  The partial safety factor  $\gamma_2=1,0$  is included  $^{3)}$  The partial safety factor  $\gamma_2=1,2$  is included  $^{4)}$  See annex 2

Table 12: Characteristic values to shear load fischer internal threaded anchors RG MI

Size				M 8	M 10	M 12	M 16	M 20
Steel failure without le	ver arm	_						
		Property	5.8 [kN]	9,2	14,5	21,1	39,2	62
Characteristic	V		8.8 [kN]	14,6	23,2	33,7	54,0	90
resistance	$V_{Rk,s}$	Property	A4 [kN]	12,8	20,3	29,5	54,8	86
		class 70	C [kN]	12,8	20,3	29,5	54,8	86
		Property	5.8 [-]			1,25		
Partial safety	$\gamma_{Ms,V}$	class				1,25		
factor	* 1015, 0	Property				1,56		
		class 70	C [-]			1,25		
Steel failure with lever	arm							
		Property	5.8 [Nm]	20	39	68	173	337
Characteristic	$M^O_{Rk,s}$		8.8 [Nm]	30	60	105	266	519
bending moment	IVI <sub>Rk,s</sub>	Property	A4 [Nm]	26	52	92	232	454
		class 70	C [Nm]	26	52	92	232	454
		Property	5.8 [-]			1,25		
Partial safety	$\gamma_{Ms.V}$		8.8 [-]			1,25		
factor	¹ Ms,V	Property	A4 [-]			1,56		
		class 70	C [-]			1,56		
Concrete pryout failure								
Factor k in Equation (5.7 Report TR 029, Section		ıl	[-]			2,0		
Partial safety factor		γ <sub>Mcp</sub> <sup>1)</sup>	[-]			1,5 <sup>2)</sup>		
Concrete edge failure				See Technical Report TR 029, Section 5.2.3.4				
Partial safety factor		γ <sub>Mc</sub> 1)	[-]			1,5 <sup>2)</sup>		
						_		

<sup>1)</sup> In absence of other national regulations.

Table 13: Displacements of fischer internal threaded anchors RG MI to tension load

Size		M 8	M 10	M 12	M 16	M 20
Non-cracked concrete and cracked concrete; temperature range I to II						
Displacement	$\delta_{NO}$ [mm/(N/mm <sup>2</sup> )]	0,09	0,10	0,10	0,11	0,13
Displacement	$\delta_{N\infty}$ [mm /(N/mm²)]	0,13	0,15	0,15	0,17	0,19

Calculation of characteristic displacement with  $\delta_{_{N}} = (\delta_{_{N0}} \cdot \tau_{_{Sd}}) / 1.4$ 

Table 14: Displacements of fischer internal threaded anchors RG MI to shear load

Size	M 8	M 10	M 12	M 16	M 20
Displacement $\delta_{_{ extsf{VO}}}$ [m	nm/kN] 0,12	0,09	0,08	0,07	0,05
Displacement $\delta_{v_{\infty}}$ [m	m/kN] 0,18	0,14	0,12	0,10	0,08

Calculation of characteristic displacement with  $\delta_{\text{v}} = (\delta_{\text{vo}} \cdot \text{V}_{\text{Sd}}) \, / \, 1,4$ 

1	fischer injection system FIS EM cc	Annex 13
Doc: FIS EM cc-03-1	fischer Internal threaded anchors RG MI Characteristic values to shear load Displacements	of European technical approval ETA-11/0216

<sup>&</sup>lt;sup>2)</sup> The partial safety factor  $\gamma_2 = 1.0$  is included.

Table 15: Characteristic values to tension load reinforcing bars

Size		Ød	8	10	12	14	16	18	20	22	24	25	26	28	30	32	34	36	40
Steel failure																			
Characteristic resistance reinforcing bars <sup>5)</sup>	e	N <sub>Rk,s</sub> [kN]	28	44	63	85	111	140	173	209	249	270	2 <b>9</b> 2	339	389	443	499	560	69 ·
Partial safety factor		γ <sub>Ms,N</sub> [-]									1,4								
Combined pullout and o	concre	te cone f	ailuı	re							_								
Diameter for calculation		d [mm]	8	10	12	14	16	18	20	22	24	25	26	28	30	32	34	36	40
Characteristic bond res	sistanc	e in non-	crac	ked	con	cret	e C2	0/2	5										
Temperature range (14) (60°C / 35°C)	τ <sub>Ak,ucr</sub> [	N/mm²]	16	15	15	14	14	14	13	13	13	13	13	13	12	12	12	12	12
Temperature range II <sup>4)</sup> (72°C / 50°C)	τ <sub>Rk,ucr</sub> [	N/mm²]	13	12	12	12	11	11	11	11	11	10	10	10	10	10	10	9,5	9,5
Characteristic bond res	istanc	e in cracl	ced	cond	rete	C2	0/2!	5											
Temperature range I <sup>4)</sup> (60C / 35°C)	τ <sub>Rk,cr</sub> [	N/mm²]	7	7	7	7	7	7	7	7	7	7	7	7	7	5	5	5	5
Temperature range II <sup>4)</sup> (72°C / 50°C)	τ <sub>Rk,cr</sub> [	N/mm²]	6	6	6	6	6	6	6	6	6	6	6	6	6	4	4	4	4
	C25	30 [-]									1,02								
		)/37 [-]									1,04								
Increasing		/45 [-]									1,06								
factors for $\tau_{Rk}$	040	/50 [-]									1,07								
	-	/55 [-]									1,08								
	C50	)/60 [-]									1,09								
Splitting failure																			
Education of	h /	h <sub>ef</sub> ≥ 2,0								1	,0 h	ef							
Edge distance c <sub>cr,sp</sub> [mm] 2,	.0 > h /	h <sub>ef</sub> >1,3							-	4,6 h									
	h /	h <sub>ef</sub> ≤ 1,3									26 h								
Spacing	S <sub>cr,sp</sub>	[mm]								2	C <sub>cr,s</sub>								
Partial safety factor γ <sub>Mp</sub> =		1) [-]		1,	,5 <sup>2)</sup>							1,8	3 <sup>3)</sup>						

<sup>1)</sup> In absence of other national regulations.

	fischer injection system FIS EM cc	Annex 14	
Joc: FIS EM cc-03-11	Reinforcing bars Characteristic values to tension load	of European technical approval ETA-11/0216	

<sup>&</sup>lt;sup>2)</sup> The partial safety factor  $\gamma_2 = 1.0$  is included <sup>3)</sup> The partial safety factor  $\gamma_2 = 1.2$  is included

<sup>4)</sup> See annex 2

<sup>&</sup>lt;sup>5)</sup> The values given in Table 15 are valid for reinforcing bars with  $f_{uk} = 550 \text{ N/mm}^2$  and  $f_{vk} = 500 \text{ N/mm}^2$ . Other reinforcing bars have to be calculated according to TR 029, Equation (5.1).

Page 24 of t	he Euro	pea	an te	echr	ical	app	rova	al E	TA-	11/	'02 <i>'</i>	l 6, i	ssue	ed o	า 10	Jun	e 20	11		
Table 16:	Chara	cte	risti	c val	ues	to sl	nea	r loa	ad r	ein	forci	na l	oars	1)						
Size	Ød	8	10	12						22			26		3	0 :	32	34	36	40
Steel failure	without l	eve	r arn	า								1				'				
Charac- teristic V resistance	/ <sub>Rk,s</sub> [kN]	13,8	21,6	31,	1 42,4	4 55,	.3 7	0	87	105	125	135	146	5 170	) 19	95 2	221	250	280	346
Partial safety factor	γ <sub>Ms,V</sub> [-]		1,5																	
Steel failure	with leve	r ar	m	m																
Charac- teristic M resistance	l <sup>0</sup> <sub>Rk,s</sub> [Nm]	33	65	11:	2 178	3 26	5 37	78 5	18	690	896	1012	2113	9 142	2 17	49 2	123 2	2547	3023	4147
Partial safety factor	γ <sub>Ms,V</sub> [-]		1,5																	
Concrete pry	out failui	e																		
Factor k in Eq (5.7) of Techn Report TR 02 Section 5.2.3	ical 9, [-]		2,0																	
Partial safety factor	γ <sub>Mcp</sub> <sup>2)</sup> [-]										1,	5 <sup>3)</sup>								
Concrete edg failure	le					Se	е Те	chni	cal I	Rep	ort T	R 02	9, Se	ction	5.2	3.4			_	
Partial safety factor	γ <sub>Mc</sub> <sup>2)</sup> [-]										1,	5 <sup>3)</sup>								
Other reinfo <sup>2)</sup> In absence <sup>3)</sup> The partial s	orcing ba of other r safety fac	rs h natio	able 16 are valid for reinforcing bars with $f_{uk} = 550 \text{ N/mm}^2$ and $f_{yk} = 500 \text{ N/mm}^2$ . It is have to be calculated according to TR 029, Equation (5.1). In a strict the property of the propert																	
Size	J.op.acc	Ø	8	10	12	14	16	18			-	-	25	26	28	30	32	34	36	40
Non-cracked	concrete		_											20	28	30	32	34	30	40
Displace- [	mm	1,			0,09			T			Ť			0.12	O 12	<u>ე 12</u>	013	0.14	0.14	0.15
ment <sup>o</sup> <sub>No</sub> L	(N/mm²) mm	1		0,00	5,55	-,00		5, 10				, \	-,	-,	-, 10	5,10	5,10	0,14	5,14	5,10

Size	Ø	8	10	12	14	16	18	20	22	24	25	26	28	30	32	34	36	40
Non-cracked concrete and cracked concrete; temperature range I to II																		
Displace- ment $\delta_{N0}$ $\frac{mm}{(N/mm^2)}$	<u>,</u>	0,07	0,08	0,09	0,09	0,10	0,10	0,11	0,11	0,12	0,12	0,12	0,13	0,13	0,13	0,14	0,14	0,15
$\begin{array}{cc} \text{Displace} & \text{mm} \\ \text{ment} & \delta_{\text{N}\infty} & \text{(N/mm}^2 \end{array}$	<u> </u>	0,11	0,12	0,13	0,14	0,15	0,16	0,16	0,17	0,18	0,18	0,18	0,19	0,19	0,20	<b>0,2</b> 0	0,21	0,22

Calculation of characteristic displacement with  $\delta_{\rm N}$  =  $(\delta_{\rm NO} \cdot \tau_{\rm Sd})/1.4$ 

Table 18: Displacements of reinforcing bars to shear load

Size		Ø	8	10	12	14	16	18	20	22	24	25	26	28	30	32	34	36	40
Displace- ment	$\delta_{\text{vo}}$	[mm/kN]	0,18	0,15	0,12	0,10	0,09	0,08	0,07	0,07	0,06	0,06	0,06	0,05	0,05	0,05	0,05	0,05	0,04
Displace- ment	$\delta_{_{\text{V}\infty}}$	[mm/kN]	0,27	0,22	0,18	0,16	0,14	0,12	0,11	0,10	0,09	0,09	0,08	0,08	0,07	0,06	0,06	0,06	0,05

Calculation of characteristic displacement with  $\delta_{\rm V}$  = ( $\delta_{\rm V0}$  •  $\rm V_{\rm Sd}$ )/1,4

	fischer injection system FIS EM cc	Annex 15
M cc-03-1	Reinforcing bars Characteristic values to shear load	of European technical approval
Doc: FIS	Displacements	ETA-11/0216

Table 19: Characteristic values to tension load fischer rebar anchor FRA

Size		M12	M16	M20	M24				
Steel failure			'						
Characteristic resistance	N <sub>Ak,s</sub> [kN]	68	126	196	283				
Partial safety factor	γ <sub>Ms,N</sub> [-]	1,56							
Combined pullout and concrete									
Diameter for calculation	d [mm]	12	16	20	25				
Characteristic bond resistance	in non-cracked concre	te C20/25							
Temperature range I <sup>4)</sup> (60°C / 35°C)	τ <sub>Rk,uer</sub> [N/mm²]	15	14	13	13				
Temperature range II <sup>4)</sup> (72°C / 50°C)	τ <sub>Rk,ucr</sub> [N/mm²]	12	11	11	11				
Characteristic bond resistance	in cracked concrete C	20/25			·				
Temperature range I <sup>4)</sup> (60C / 35°C)	τ <sub>Rk,cr</sub> [N/mm²]		7						
Temperature range II <sup>4)</sup> (72°C / 50°C)	τ <sub>Rk,cr</sub> [N/mm²]		6						
	C25/30 [-]		1,02	2					
	C30/37 [-]		1,04						
Increasing	C35/45 [-]		1,06		_				
factors for $\tau_{Rk}$	C40/50 [-]		1,0						
	C45/55 [-]		1,08						
	C50/60 [-]		1,09	<del>)</del>					
Splitting failure									
	h / h <sub>ef</sub> ≥ 2,0		1,0	h <sub>ef</sub>					
Edge distance c <sub>cr.sp</sub> [mm]	2,0 > h / h <sub>ef</sub> > 1,3		4,6 h <sub>ef</sub> -	1,8 h					
	h / h <sub>ef</sub> ≤ 1,3		2,26						
Spacing	S <sub>cr,sp</sub> [mm]		2 c <sub>cr</sub>	.sp					
Partial safety factor γ <sub>Mp</sub> =	$= \gamma_{Mc} = \gamma_{Msp}^{1)} \qquad [-]$	1,5 <sup>2)</sup>		1,8 <sup>3)</sup>					

	fischer injection system FIS EM cc	Annex 16
Joc: FIS EM cc-03-11	fischer rebar anchors FRA Characteristic values to tension load	of European technical approval ETA-11/0216

<sup>&</sup>lt;sup>1)</sup> In absence of other national regulations. <sup>2)</sup> The partial safety factor  $\gamma_2 = 1,0$  is included <sup>3)</sup> The partial safety factor  $\gamma_2 = 1,2$  is included <sup>4)</sup> See annex 2

Table 20: Characteristic values to shear load fischer rebar anchor FRA

Size			M12	M16	M20	M24
Steel failure without lever arm						
Characteristic resistance	$V_{_{Rk,s}}$	[kN]	33,7	63	98	141
Partial safety factor	$\gamma_{Ms,V}$	[-]		1,:	25	
Steel failure with lever arm					_	
Characteristic bending moment	M <sup>0</sup> <sub>Rk,s</sub> [	Nm]	105	266	519	896
Partial safety factor	$\gamma_{Ms,V}$	[-]		1,:	25	
Concrete pryout failure						,
Factor k in Equation (5.7) of Technical Report TR 029, Section 5.	2.3.3 k	[-]		2,	0	
Partial safety factor	γ <sub>Mcp</sub> <sup>1)</sup>	[-]		1,!	5 <sup>2)</sup>	
Concrete edge failure			See Tech	nical Report T	R 029, Section	5.2.3.4
Partial safety factor	γ <sub>Mc</sub> 1)	[-]		1,!	5 <sup>2)</sup>	

<sup>1)</sup> In absence of other national regulations.

Table 21: Displacements of fischer rebar anchors FRA to tension load

Size	Ø	12	16	20	24
Non-cracked an	d cracked concrete; tem	perature r	ange I to II		
Displacement	$\delta_{\rm NO}$ [mm/(N/mm²)]	0,09	0,10	0,11	0,12
Displacement	$\delta_{\rm N\infty}$ [mm/(N/mm <sup>2</sup> )]	0,13	0,15	0,16	0,18

Calculation of characteristic displacement with  $\delta_{_{N}}$  = ( $\delta_{_{NO}}$  •  $\tau_{_{Sd}})$  /1,4

Table 22: Displacements of fischer rebar anchors FRA to shear load

Size		Ø	12	16	20	24
Displacement	$\boldsymbol{\delta}_{vo}$	[mm/kN]	0,12	0,09	0,07	0,06
Displacement	$\delta_{_{\text{V}\infty}}$	[mm/kN]	0,18	0,14	0,11	0,09

Calculation of characteristic displacement with  $\delta_{\rm V}$  = ( $\delta_{\rm VO}$  • V<sub>Sd</sub>) /1,4

fischer injection system FIS EM cc	Annex 17
fischer rebar anchors FRA	of European
Characteristic values to shear load	technical approval
Displacements	ETA-11/0216

Doc: FIS EM cc-03-11

 $<sup>^{2)}</sup>$  The partial safety factor  $\gamma_{2}$  = 1,0 is included.