#### Deutsches Institut für Bautechnik

#### Zulassungsstelle für Bauprodukte und Bauarten

#### **Bautechnisches Prüfamt**

Eine vom Bund und den Ländern gemeinsam getragene Anstalt des öffentlichen Rechts

Kolonnenstraße 30 B D-10829 Berlin Tel.: + 49 30 78730-0 Fax: +493078730-320 E-Mail: dibt@dibt.de

www.dibt.de





Mitglied der EOTA Member of EOTA

# **European Technical Approval ETA-07/0025**

English translation prepared by DIBt - Original version in German language

Handelsbezeichnung Trade name

Zulassungsinhaber Holder of approval

Zulassungsgegenstand und Verwendungszweck

Generic type and use of construction product

Geltungsdauer:

Validity:

verlängert vom extended from bis

vom

from bis

to

to

Herstellwerk Manufacturing plant fischer Hochleistungsanker FH II und FH II A4 fischer High-Performance Anchor FH II and FH II A4

fischerwerke GmbH & Co. KG

Weinhalde 14-18 72178 Waldachtal DEUTSCHLAND

Kraftkontrolliert spreizender Metalldübel in den Größen 10, 12, 15,

18, 24, 28 und 32 zur Verankerung im Beton

Torque-controlled expansion anchor of sizes 10, 12, 15, 18, 24, 28 and 32 for use in concrete

19 February 2009

31 January 2012

7 October 2011

7 October 2016

fischerwerke

Diese Zulassung umfasst This Approval contains

18 Seiten einschließlich 10 Anhänge 18 pages including 10 annexes





Page 2 of 18 | 7 October 2011

## I LEGAL BASES AND GENERAL CONDITIONS

- 1 This European technical approval is issued by Deutsches Institut für Bautechnik in accordance with:
  - Council Directive 89/106/EEC of 21 December 1988 on the approximation of laws, regulations and administrative provisions of Member States relating to construction products<sup>1</sup>, modified by Council Directive 93/68/EEC<sup>2</sup> and Regulation (EC) N° 1882/2003 of the European Parliament and of the Council<sup>3</sup>;
  - Gesetz über das In-Verkehr-Bringen von und den freien Warenverkehr mit Bauprodukten zur Umsetzung der Richtlinie 89/106/EWG des Rates vom 21. Dezember 1988 zur Angleichung der Rechts- und Verwaltungsvorschriften der Mitgliedstaaten über Bauprodukte und anderer Rechtsakte der Europäischen Gemeinschaften (Bauproduktengesetz - BauPG) vom 28. April 1998<sup>4</sup>, as amended by law of 31 October 2006<sup>5</sup>;
  - Common Procedural Rules for Requesting, Preparing and the Granting of European technical approvals set out in the Annex to Commission Decision 94/23/EC<sup>6</sup>;
  - Guideline for European technical approval of "Metal anchors for use in concrete Part 2: Torque controlled expansion anchors ", ETAG 001-02.
- Deutsches Institut für Bautechnik is authorized to check whether the provisions of this European technical approval are met. Checking may take place in the manufacturing plant. Nevertheless, the responsibility for the conformity of the products to the European technical approval and for their fitness for the intended use remains with the holder of the European technical approval.
- This European technical approval is not to be transferred to manufacturers or agents of manufacturers other than those indicated on page 1, or manufacturing plants other than those indicated on page 1 of this European technical approval.
- This European technical approval may be withdrawn by Deutsches Institut für Bautechnik, in particular pursuant to information by the Commission according to Article 5(1) of Council Directive 89/106/EEC.
- Reproduction of this European technical approval including transmission by electronic means shall be in full. However, partial reproduction can be made with the written consent of Deutsches Institut für Bautechnik. In this case partial reproduction has to be designated as such. Texts and drawings of advertising brochures shall not contradict or misuse the European technical approval.
- The European technical approval is issued by the approval body in its official language. This version corresponds fully to the version circulated within EOTA. Translations into other languages have to be designated as such.

Official Journal of the European Communities L 40, 11 February 1989, p. 12

Official Journal of the European Communities L 220, 30 August 1993, p. 1

Official Journal of the European Union L 284, 31 October 2003, p. 25

Bundesgesetzblatt Teil I 1998, p. 812

Bundesgesetzblatt Teil I 2006, p. 2407, 2416

Official Journal of the European Communities L 17, 20 January 1994, p. 34



Page 3 of 18 | 7 October 2011

## II SPECIFIC CONDITIONS OF THE EUROPEAN TECHNICAL APPROVAL

## 1 Definition of product and intended use

## 1.1 Definition of the construction product

The fischer High-Performance Anchor FH II is an anchor made of galvanised steel (sizes 10, 12, 15, 18, 24, 28 and 32) or stainless steel (sizes 10, 12, 15, 18 and 24) which is placed into a drilled hole and anchored by torque-controlled expansion.

An illustration of the product and intended use is given in Annex 1.

### 1.2 Intended use

The anchor is intended to be used for anchorages for which requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 of Council Directive 89/106 EEC shall be fulfilled and failure of anchorages made with these products would cause risk to human life and/or lead to considerable economic consequences.

The anchor may be used for anchorages with requirements related to resistance to fire.

The anchor is to be used only for anchorages subject to static or quasi-static loading in reinforced or unreinforced normal weight concrete of strength classes C20/25 at minimum and C50/60 at most according to EN 206: 2000-12. It may be anchored in cracked and non-cracked concrete.

## fischer High-Performance Anchor FH II made of galvanised steel:

The anchor may only be used in structures subject to dry internal conditions.

## fischer High-Performance Anchor FH II A4 made of stainless steel:

The anchor made of stainless steel A4 may be used in structures subject to dry internal conditions and also in structures subject to external atmospheric exposure (including industrial and marine environment), or exposure in permanently damp internal conditions, if no particular aggressive conditions exist. Such particular aggressive conditions are e.g. permanent, alternating immersion in seawater or the splash zone of seawater, chloride atmosphere of indoor swimming pools or atmosphere with extreme chemical pollution (e.g. in desulphurization plants or road tunnels where de-icing materials are used).

The provisions made in this European technical approval are based on an assumed working life of the anchor of 50 years. The indications given on the working life cannot be interpreted as a guarantee given by the producer, but are to be regarded only as a means for choosing the right products in relation to the expected economically reasonable working life of the works.



Page 4 of 18 | 7 October 2011

## 2 Characteristics of the product and methods of verification

## 2.1 Characteristics of the product

The anchor corresponds to the drawings and provisions given in Annexes 2 and 3. The characteristic material values, dimensions and tolerances of the anchor not given in Annexes 2 and 3 shall correspond to the respective values laid down in the technical documentation<sup>7</sup> of this European technical approval.

Regarding the requirements concerning safety in case of fire it is assumed that the anchor meets the requirements of class A1 in relation to reaction to fire in accordance with the stipulations of the Commission decision 96/603/EC, amended by 2000/605/EC.

The characteristic values for the design of anchorages are given in Annexes 3 to 7.

The characteristic values for the design of anchorages regarding resistance to fire are given in Annexes 8 and 9. They are valid for use in a system that is required to provide a specific fire resistance class.

Each anchor is marked according to Annex 1.

The anchor shall only be supplied as a complete unit.

### 2.2 Methods of verification

The assessment of fitness of the anchor for the intended use in relation to the requirements for mechanical resistance and stability and safety in use in the sense of the Essential Requirements 1 and 4 has been made in accordance with the "Guideline for European technical approval of Metal Anchors for Use in Concrete", Part 1 "Anchors in general" and Part 2 "Torque-controlled expansion anchors", on the basis of Option 1.

The assessment of the anchor for the intended use in relation to the requirements for resistance to fire has been made in accordance with the Technical Report TR 020 "Evaluation of anchorages in concrete concerning resistance to fire".

In addition to the specific clauses relating to dangerous substances contained in this European technical approval, there may be other requirements applicable to the products falling within its scope (e.g. transposed European legislation and national laws, regulations and administrative provisions). In order to meet the provisions of the Construction Products Directive, these requirements need also to be complied with, when and where they apply.

Z43088.11 8.06.01-394/10

7

The technical documentation of this European technical approval is deposited at the Deutsches Institut für Bautechnik and, as far as relevant for the tasks of the approved bodies involved in the attestation of conformity procedure, is handed over to the approved bodies.



### Page 5 of 18 | 7 October 2011

## 3 Evaluation and attestation of conformity and CE marking

## 3.1 System of attestation of conformity

According to the decision 96/582/EG of the European Commission<sup>6</sup> the system 2(i) (referred to as system 1) of attestation of conformity applies.

This system of attestation of conformity is defined as follows:

System 1: Certification of the conformity of the product by an approved certification body on the basis of:

- (a) Tasks for the manufacturer:
  - factory production control;
  - (2) further testing of samples taken at the factory by the manufacturer in accordance with a prescribed control plan;
- (b) Tasks for the approved body:
  - (3) initial type-testing of the product;
  - (4) initial inspection of factory and of factory production control;
  - (5) continuous surveillance, assessment and approval of factory production control.

Note: Approved bodies are also referred to as "notified bodies".

## 3.2 Responsibilities

## 3.2.1 Tasks of the manufacturer

## 3.2.1.1 Factory production control

The manufacturer shall exercise permanent internal control of production. All the elements, requirements and provisions adopted by the manufacturer shall be documented in a systematic manner in the form of written policies and procedures, including records of results performed. This production control system shall insure that the product is in conformity with this European technical approval.

The manufacturer may only use initial/ raw/ constituent materials stated in the technical documentation of this European technical approval.

The factory production control shall be in accordance with the control plan which is part of the technical documentation of this European technical approval. The control plan is laid down in the context of the factory production control system operated by the manufacturer and deposited at Deutsches Institut für Bautechnik<sup>9</sup>.

The results of factory production control shall be recorded and evaluated in accordance with the provisions of the control plan.

#### 3.2.1.2 Other tasks of manufacturer

The manufacturer shall, on the basis of a contract, involve a body which is approved for the tasks referred to in section 3.1 in the field of anchors in order to undertake the actions laid down in section 3.2.2. For this purpose, the control plan referred to in sections 3.2.1.1 and 3.2.2 shall be handed over by the manufacturer to the approved body involved.

The manufacturer shall make a declaration of conformity, stating that the construction product is in conformity with the provisions of this European technical approval.

Z43088.11

Official Journal of the European Communities L 254 of 08.10.1996.

The control plan is a confidential part of the documentation of the European technical approval, but not published together with the ETA and only handed over to the approved body involved in the procedure of attestation of conformity. See section 3.2.2.



Page 6 of 18 | 7 October 2011

## 3.2.2 Tasks of approved bodies

The approved body shall perform the

- initial type-testing of the product,
- initial inspection of factory and of factory production control,
- continuous surveillance, assessment and approval of factory production control,

in accordance with the provisions laid down in the control plan.

The approved body shall retain the essential points of its actions referred to above and state the results obtained and conclusions drawn in a written report.

The approved certification body involved by the manufacturer shall issue an EC certificate of conformity of the product stating the conformity with the provisions of this European technical approval.

In cases where the provisions of the European technical approval and its control plan are no longer fulfilled the certification body shall withdraw the certificate of conformity and inform Deutsches Institut für Bautechnik without delay.

#### 3.3 CE marking

The CE marking shall be affixed on each packaging of the anchor. The letters "CE" shall be followed by the identification number of the approved certification body, where relevant, and be accompanied by the following additional information:

- The name and address of the producer (legal entity responsible for the manufacturer),
- The last two digits of the year in which the CE marking was affixed,
- The number of the EC certificate of conformity for the product,
- The number of the European technical approval,
- The number of the guideline for European technical approval,
- Use category (ETAG 001-1 Option 1),
- Size

# 4 Assumptions under which the fitness of the product for the intended use was favourably assessed

### 4.1 Manufacturing

The European technical approval is issued for the product on the basis of agreed data/information, deposited with Deutsches Institut für Bautechnik, which identifies the product that has been assessed and judged. Changes to the product or production process, which could result in this deposited data/information being incorrect, should be notified to Deutsches Institut für Bautechnik before the changes are introduced. Deutsches Institut für Bautechnik will decide whether or not such changes affect the approval and consequently the validity of the CE marking on the basis of the approval and if so whether further assessment or alterations to the approval shall be necessary.

### 4.2 Design of anchorages

The fitness of the anchor for the intended use is given under the following conditions:

The anchorages are designed in accordance with the "Guideline for European technical approval of Metal Anchors for Use in Concrete", Annex C, Method A under the responsibility of an engineer experienced in anchorages and concrete work.



## Page 7 of 18 | 7 October 2011

Verifiable calculation notes and drawings are taking account of the loads to be anchored.

The position of the anchor is indicated on the design drawings (e.g. position of the anchor relative to reinforcement or to supports).

The design of anchorages under fire exposure has to consider the conditions given in the Technical Report TR 020 "Evaluation of anchorages in concrete concerning resistance to fire". The relevant characteristic anchor values are given in Annexes 8 and 9. The design method covers anchors with a fire attack from one side only. If the fire attack is from more than one side, the design method may be taken only, if the edge distance of the anchor is  $c \ge 300$  mm.

Local spalling is possible at fire attack. To avoid any influence of the spalling on the anchorage, the concrete member must be designed according to prEN 1992-1-2. The members shall be made of concrete with quartzite additives and have to be protected from direct moisture; and the moisture content of the concrete has to be like in dry internal conditions respectively. The anchorage depth has to be increased for wet concrete by at least 30 mm compared to the given value in the approval.

## 4.3 Installation of anchors

The fitness for use of the anchor can only be assumed if the anchor is installed as follows:

- Anchor installation carried out by appropriately qualified personnel and under the supervision
  of the person responsible for technical matters of the site,
- Use of the anchor only as supplied by the manufacturer without exchanging the components of an anchor,
- Anchor installation in accordance with the manufacturer's specifications and drawings and using the appropriate tools,
- Checks before placing the anchor to ensure that the strength class of the concrete in which the anchor is to be placed is in the range given and is not lower than that of the concrete to which the characteristic loads apply,
- Check of concrete being well compacted, e.g. without significant voids,
- Edge distances and spacings not less than the specified values without minus tolerances.
- Positioning of the drill holes without damaging the reinforcement,
- In case of aborted hole: new drilling at a minimum distance away of twice the depth of the aborted hole or smaller distance if the aborted drill hole is filled with high strength mortar and if under shear or oblique tension load it is not in the direction of load application,
- Cleaning of the hole of drilling dust,
- Anchor installation such that the effective anchorage depth is complied with. This compliance is ensured when the embedment mark of the anchor does no more exceed the concrete surface.
- Application of the torque moment given in Annex 3 using a calibrated torque wrench.



Page 8 of 18 | 7 October 2011

## 5 Responsibility of the manufacturer

The manufacturer is responsible to ensure that the information on the specific conditions according to 1 and 2 including Annexes referred to as well as sections 4.2 and 4.3 is given to those who are concerned. This information may be made by reproduction of the respective parts of the European technical approval. In addition all installation data shall be shown clearly on the package and/or on an enclosed instruction sheet, preferably using illustration(s).

The minimum data required are:


- Diameter of drill bit.
- Thread diameter,
- Maximum thickness of the fixture,
- Minimum effective anchorage depth,
- Minimum hole depth,
- Torque moment,
- Information on the installation procedure, including cleaning of the hole, preferably by means of an illustration,
- Reference to any special installation equipment needed,
- Identification of the manufacturing batch.

All data shall be presented in a clear and explicit form.

Georg Feistel
Head of Department

beglaubigt: Baderschneider






Type hexagon screw S

FH II 10 - 32 S

FH II 10 - 24 S A4


Marking: Identifying mark of the producer, anchor identity nominal drill hole diameter / max. thickness of fixture e. g. FH II 15/25 A4



Type countersunk screw SK

FH II 10 - 18 SK


FH II 10 - 18 SK A4



Type hexagon nut B

FH II 10 - 32 B

FH II 10 - 24 B A4



Type cap nut H


FH II 10 - 24 H

FH II 10 - 24 H A4

- 1 Hexagon screw
- 2 Countersunk screw
- (3) Cap nut
- (4) Hexagon nut
- 5 Threaded rod



- 7 Distance sleeve
- 8 Expansion sleeve
- 9 Plastic sleeve
- 10 Washer
- 11) Conical washer



1) h<sub>ef</sub>: effective

effective anchorage depth.

2) t<sub>fix</sub>: thickness of fixture.
3) h<sub>1</sub>: drill hole depth.

4) h<sub>min</sub>: minimal member thickness.

<sup>5)</sup> T<sub>inst</sub>: installation torque.

fischer High-Performance Anchor FH II and FH II A4

Product and Intended use

Annex 1






Table 1: Anchor Dimensions [mm]

Table 1: Anchor Dimensions [mm]									
Anchor type FH II S, SK, B, H and FH II S, SK, B, H A4		FH II	FH II 12	FH II 15	FH II 18	FH II 24	FH II 28	FH II 32	
thread	М	=	6	8	10	12	16	20	24
diameter conical nut	d <sub>c</sub>	=	10	12	14,8	17,8	23,7	27,5	31,5
	FH II S, B		10	13	17	19	24	30	36
SW FH II	FH II SK 1)	1	4	5	6	8	-	-	-
	FHIIH	] =	13	17	17	19	24	-	- ]
SW FH II A4	FH II S, B, H A4	1	10	13	17	19	24	-	-
3VV11111A4	FH II SK A4 1)		4	5	6	8	-	_	-
t <sub>fix</sub> FH II + FH II A4 S, B, H	min		0	0	0	0	0	0	0
t <sub>fix</sub> FH II SK + FH II SK A4 <sup>1)</sup>	min		5	6	6	8	-	-	-
t <sub>fix</sub> FH II + FH II A4	max		250	250	300	350	400	500	500
length of screw / bolt	L <sub>s</sub> , L <sub>h</sub> , L <sub>b</sub> (- t <sub>fix</sub> )	≥	49	74	89	99	124	149	174
length of countersunk screw	L <sub>sk</sub> (- t <sub>fix</sub> )	2	54	79	95	107	-	-	-

<sup>1)</sup> internal hexagon

fischer High-Performance Anchor FH II and FH II A4	
Anchor types Anchor dimensions	Annex 2



Table 2: Material

Nb.	Designation	FH II	FH II A4
1	Hexagon screw 2)	Steel class 8.8; DIN EN ISO 898-11)	
2	Countersunk screw 2)	Steel class 8.8; DIN EN ISO 898-11)	Strength class 70
3	Cap nut	Steel class 8 1)	DIN EN ISO 3506
4	Hexagon nut 2)	]	
5	Threaded rod	Steel R <sub>m</sub> ≥ 800 N/mm²; R <sub>e</sub> ≥ 640 N/mm² <sup>1)</sup>	
6	Cone nut 3)	Steel EN 10277 1)	
7	Distance sleeve	Steel EN 10305 1)	EN 10088
8	Expansion sleeve	Steel EN 10139 / EN 102771)	EN 10088
9	Plastic sleeve	ABS (plastic)	
10	Washer 2)	Steel EN 10139 1)	EN 10088
11	Conical washer 2)	Steel EN 10277 1)	EN 10088

Table 3: Installation parameters

Table 5. Installation parameters									
	e FH II S, SK, B, H S, SK, B, H <b>A</b> 4		FH II 10	FH II 12	FH II 15	FH II 18	FH II 24	FH II 28	FH II 32
Nominal dr	ill hole Diameter	$d_0 = [mm]$	10	12	15	18	24	28	32
Maximum o	diameter of drill bit	$d_{cut} \leq [mm]$	10,45	12,50	15,50	18,50	24,55	28,55	32,70
Depth of dr	Depth of drill hole		55	80	90	105	125	155	180
Diameter o	f clearance hole	$d_f \leq [mm]$	12	14	17	20	26	31	35
Diameter o	Diameter of counter sunk	FH II SK	18	22	25	32	-	-	-
Depth of co	ounter sunk, 90°	FH II SK A4	5,0	5,8	5,8	8,0	-	-	-
	FHIIS		10	22,5	40	80	160	180	200
Required	FH II B		10	17,5	38	80	120	180	200
installation torque	FHIIH	T - [Nlm]	10	22,5	40	80	90	-	
Lorquo	FHIISK	$T_{inst} = [Nm]$	10	22,5	40	80	-	-	-
	FHIIS, B, HA4		15	25	40	100	160	_	-
	FH II SK A4		10	25	40	100	-	-	-

Table 4: Minimum thickness of concrete member, min. spacing and min. edge distances

Anchor type FH II S, SK, B, I and FH II S, SK, B, H A4	1	FH II 10	FH II 12	FH II 15	FH II 18	FH II 24	FH II 28	FH II 32
Min. member thickness	h <sub>min</sub> [mm]	80	120	140	160	200	250	300
Minimum spacing,	s <sub>min</sub> [mm]	40	50	60	70	80	100	120
cracked concrete	für c≥ [mm]	40	80	120	140	180	200	260
Minimum edge distance,	c <sub>min</sub> [mm]	40	50	60	70	80	100	120
cracked concrete	für s ≥ [mm]	40	80	120	160	200	220	280
Minimum spacing,	s <sub>min</sub> [mm]	40	60	70	80	100	120	160
uncracked concrete	für c ≥ [mm]	70	100	100	160	200	220	360
Minimum edge distance,	c <sub>min</sub> [mm]	40	60	70	80	100	120	180
uncracked concrete	für s ≥ [mm]	70	100	140	200	220	240	380

Intermediate values may be calculated by linear interpolation.

fischer High-Performance Anchor FH II and FH II A4 Annex 3 Materials / Component Installation parameters / Member dimensions

 $<sup>^{1)}</sup>$  Galvanised according to EN ISO 4042,  $\geq 5~\mu m$   $^{2)}$  with functional coating FH II 10 - 24 conical washer + FH II + FH II A4 10-24 washer, FH II 28 + 32 and FH II 10 + 12 A4 hexagon screw, FH II A4 countersunk screw, FH II 28 – 32 hexagon nut  $^{3)}$  with functional coating FH II 10 – 32 + FH II A4 10 - 24 conical nut.





Table 5: Design me characteris					Annex	С				
Anchor type FH II S, SK, B, H and FH II S, SK, B, H A4			FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 <sup>3)</sup>	FH II 28 <sup>4)</sup>	FH I 32 <sup>4)</sup>	
Steel failure										
Characteristic resistance		-								
FH II	$N_{Rk,s}$	[kN]	16,1	29,3	46,4	67,4	125,3	195,8	282	
FH II A4	$N_{Rk,s}$	[kN]	14,1	25,6	40,6	59,0	109,7	-	-	
Partial safety factor	γ <sub>Ms</sub> 1)					1,5				
Pullout failure										
Characteristic resistance								•		
cracked concrete FH II and FH II A4	$N_{Rk,p}$ [kN]	C20/25	7,5	12	16	25	2)	2)	2)	
non-cracked concrete FH II	N <sub>Rk,p</sub> [kN]	C20/25	2)	2)	2)	2)	2)	2)	2)	
non-cracked concrete FH II A4	N <sub>Rk,p</sub> [kN]	C20/25	2)	20	2)	2)	2)	-	-	
		C25/30				1,10				
		C30/37	1,22							
Increasing factors for N <sub>Bk,p</sub>	Ψο	C35/45				1,34				
More againg Table 10. TARK,p	Ψ¢	C40/50				1,41				
		C45/55				1,48				
		C50/60				1,55				
Partial safety factor	γ <sub>Mp</sub> 1)			-	_	1,5 <sup>5)</sup>				
Concrete cone failure and s		failure								
Effective anchorage depth	h <sub>ef</sub>	[mm]	40	60	70	80	100	125	150	
Spacing	S <sub>cr,N</sub>	[mm]	120	180	210	240	300	375	450	
Edge distance	c <sub>cr,N</sub>	[mm]	60	90	105	120	150	187,5	225	
Spacing (splitting)	s <sub>cr,sp</sub>	[mm]	190	300	320	340	380	480	570	
Edge distance (splitting)	C <sub>cr,sp</sub>	[mm]	95	150	160	170	190	240	285	
Partial safety factor γ <sub>Mc</sub> 1)						1,5 <sup>5)</sup>				

fischer High-Performance Anchor FH II and FH II A4	
Design method A Characteristic values for tension loads	Annex 4

<sup>1)</sup> In absence of other national regulations.
2) Pullout failure is not decisive.
3) Only FH II S, FH II B and FH II H + FH II S A4, FH II B A4 and FH II H A4.
4) Only FH II S and FH II B.
5)

<sup>&</sup>lt;sup>5)</sup> The partial safety factor  $\gamma_2 = 1,0$  is included.



Table 6: Displacements under tension loads, FH II

Anchor type FH II S, SK, B, H			FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 <sup>1)</sup>	FH II 28 <sup>2)</sup>	FH II 32 <sup>2)</sup>
Tension load cracked concrete	N	[kN]	3,6	5,7	7,6	11,9	17,1	24,0	31,5
Corresponding displacements	$\delta_{\text{N0}}$	[mm]	0,8	0,2	0,3	0,4	0,6	0,7	0,7
Corresponding displacements	$\delta_{N\infty}$	[mm]	1,7	0,9	1,3	1,6	1,8	1,3	1,1
Tension load uncracked concrete	N	[kN]	6,0	11,2	14,1	17,2	24,0	33,6	44,2
Corresponding displacements	$\delta_{\text{N0}}$	[mm]	0,6	0,1	0,2	0,3	0,2	0,3	0,3
Corresponding displacements	$\delta_{N\infty}$	[mm]	1,7	0,9	1,3	1,6	1,8	1,3	1,1

 $<sup>^{1)}</sup>$  Only FH II S, FH II B and FH II H.  $^{2)}$  Only FH II S and FH II B.

Table 7: Displacements under tension loads, FH II A4

Anchor type FH II S, SK, B, H A4			FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 1)
Tension load cracked concrete	N	[kN]	3,6	5,7	7,6	11,9	17,1
Corresponding displacements	$\delta_{\text{NO}}$	[mm]	1,0	1,0	1,0	1,0	1,0
Corresponding displacements	$\delta_{N\infty}$	[mm]	1,7	1,6	1,6	1,4	1,1
Tension load uncracked concrete	N	[kN]	6,0	11,2	14,1	17,2	24,0
Corresponding displacements	$\delta_{\text{N0}}$	[mm]	0,6	1,0	1,0	1,0	1,0
Corresponding displacements	$\delta_{N\infty}$	[mm]	1,7	1,6	1,6	1,4	1,1

 $<sup>^{\</sup>rm 1)}$  Only FH II S A4, FH II B A4 and FH II H A4.

fischer High-Performance Anchor FH II and FH II A4 Annex 5 Design method A Characteristic displacements for tension loads






Table 8: Design method A, characteristic values for shear loads										
Anchor type FH II S, SK, B, H and FH II S, SK, B, H A4		FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 <sup>3)</sup>	FH II 28 <sup>4)</sup>	FH II		
Steel failure without lever arr	n									
Characteristic resistance										
FH II S + FH II SK	V <sub>Rk,s</sub> [kN]	18	33	59	76	146	174	217		
FH II B + FH II H	V <sub>Rk,s</sub> [kN]	16	27	41	62	119	146	169		
FH II S A4, FH II SK A4, FH II B A4, FH II H A4	V <sub>Rk,s</sub> [kN]	18	28	43	66	119	-	-		
Partial safety factor	γ <sub>Ms</sub> 1)	1,25								
Steel failure with lever arm										
Characteristic bending resistance FH II	M <sup>0</sup> <sub>Rk,s</sub> [Nm]	12	30	60	105	266	518	896		
Characteristic bending resistance FH II A4	M <sup>0</sup> <sub>Rk,s</sub> [Nm]	11	26	52	92	232	-	-		
Partial safety factor	γMs 1)			1	1,25	I	<del></del>			
Concrete pryout failure						_				
Factor in equation (5.6) of ETAG 001 Annex C, 5.2.3.3	k	1,0			2	,0				
Partial safety factor	γ <sub>Mcp</sub> 1)		1,5 <sup>2)</sup>							
Concrete edge failure										
Effective length of anchor under shear load	l <sub>f</sub>	40	60	70	80	100	125	150		
Effective diameter of anchor	d <sub>nom</sub> [mm]	10	12	15	18	24	28	32		
Partial safety factor	γ <sub>Mc</sub> <sup>1)</sup>			<u> </u>	1,5 2)	1				

fischer High-Performance Anchor FH II and FH II A4	
Design method A Characteristic values for shear loads, displacements	Annex 6

<sup>&</sup>lt;sup>1)</sup> In absence of other national regulations.
<sup>2)</sup> The partial safety factor  $\gamma_2$  = 1,0 is included.
<sup>3)</sup> Only FH II S, FH II B and FH II H + FH II S A4, FH II B A4 and FH II H A4.
<sup>4)</sup> Only FH II S and FH II B.



Displacements under shear loads FH II S and SK 2) Table 9:

Anchor type FH II S and FH II SK			FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 <sup>1)</sup>	FH II 28 <sup>1)</sup>	FH II 32 <sup>1)</sup>
Shear load in cracked and non-cracked concrete	V	[kN]	10,3	18,9	33,7	43,4	83,4	99,4	124,0
Corresponding	$\delta_{V0}$	[mm]	2,4	2,7	4,4	5,0	7,0	6,0	8,0
displacements	$\delta_{V\infty}$	[mm]	3,6	4,1	6,6	7,5	10,5	9,0	12,0

<sup>1)</sup> Only FH II S.

Displacements under shear loads FH II B and H 2)

Anchor type: FH II B and FH II H			FH II 10	FH II 12	FH II 15	FH II 18	FH II 24	FH II 28 <sup>1)</sup>	FH II 32 <sup>1)</sup>
Shear load in cracked and non-cracked concrete	V	[kN]	8,9	15,4	23,4	35,4	68,0	83,4	96,6
Corresponding	δνο	[mm]	2,2	2,3	3,0	5,0	7,0	5,0	5,0
displacements	$\delta_{V\infty}$	[mm]	3,3	3,5	4,5	7,5	10,5	7,5	7,5

Displacements under shear loads FH II S A4, FH II SK A4, FH II B A4 and FH II H A4  $^{\rm 2)}$ Table 11:

Anchor type: FH II S A4, FH FH II B A4, FH II H A4	II SK	A4,	FH II 10	FH II 12	FH II 15	FH II 18	FH II 24 <sup>1)</sup>
Shear load in cracked and non-cracked concrete	V	[kN]	10,3	16,0	24,6	37,7	68,0
Corresponding	$\delta_{V0}$	[mm	3,5	3,5	3,7	5,7	9,0
displacements	$\delta_{V\infty}$	[mm	5,3	5,3	5,6	8,6	13,5

fischer High-Performance Anchor FH II and FH II A4 Annex 7 Design method A Characteristic displacements for shear loads

<sup>&</sup>lt;sup>2)</sup> Tolerance of clearance hole not included in the displacements.

<sup>&</sup>lt;sup>2)</sup> Tolerance of clearance hole not included in the displacements.

<sup>1)</sup> Only FH II S A4, FH II B A4 and FH II H A4.
2) Tolerance of clearance hole not included in the displacements.



R30, Fire resistance 30 minutes	j		FH II   10	FH II 12	FH II	1		FHII	FHT	
Steel failure			1 10	2	15	18	24	28	32	
Characteristic resistance	$N_{Rk,s,fi,30}$	(kN)	0,2	2,0	3,2	4,8	8,9	13,9	20,0	
Pull-out failure	س, ۱۱, ج ۲۳۸	1100	1 0,-	L, v		-1,0	0,0	10,0	20,0	
Characteristic resistance	Tki	# N 1 N	Τ.,		T					
in concrete C20/25 to C50/60	N <sub>Fk.p,fi,30</sub>	(kN)	1,8	3,0	4,0	6,3	9,0	12,6	16,5	
Concrete cone failure					1			<u></u>		
Characteristic resistance	N10	(kN)	$T_{q}$	50	71	10.2	100	21.4	40.6	
in concrete C20/25 to C50/60	N <sup>0</sup> Rk,cfi,30	(KIV)	1,8	5,0	7,4	10,3	18,0	31,4	49,6	
R60, Fire resistance 60 minutes	FH II 10	FH II	FH II 15	FH II	FH II 24	FH II 28	FH II			
Steel failure	1-1100								L <del>\</del>	
Characteristic resistance	$N_{Pk,s,fi,60}$	(kN)	0,2	1,3	2,3	3,9	7,3	11,3	16,3	
Pull-out failure							<u>.                                    </u>			
Characteristic resistance in concrete C20/25 to C50/60	N <sub>Fk.p.fi,60</sub>	(kN)	1,8	3,0	4,0	6,3	9,0	12,6	16,5	
Concrete cone failure		_								
Characteristic resistance	N <sup>0</sup> <sub>Rk,cfi,60</sub>	(kN)	1,8	5,0	7,4	10,3	18,0	31,4	49,6	
in concrete C20/25 to C50/60	, uk'ch'oo	(1.1.7)	.,-	0,0	,,,	10,0	10,0	0.,.	70,0	
R90, Fire resistance 90 minutes			FH II 10	FH II 12	FH II	FH    18	FH II 24	FH II	FH II 32	
Steel fai <b>lure</b>						, 700				
Characteristic resistance	$N_{\rm Fk,s,fi,90}$	(kN)	0,1	0,6	1,4	3,0	5,6	8,8	12,6	
Pull-out failure										
Characteristic resistance in concrete C20/25 to C50/60	N <sub>Fkp,fi,90</sub>	(kN)	1,8	3,0	4,0	6,3	9,0	12,6	16,5	
Concrete cone failure							·			
Characteristic resistance	T <sub>N1</sub> 0	(kN)	1,8	5,0	7,4	10,3	18,0	31,4	40.6	
in concrete C20/25 to C50/60	N <sup>0</sup> <sub>Rk,cfi,90</sub>	(KIN)	1,0	5,0	/,4	10,3	10,0	31,4	49,6	
R120, Fire resistance 120 minute	^^		FH II	FHIII	FH II	FHII	FHII	FH II	FH II	
<u> </u>	- <del></del>		10	12	15	18	24	28	32	
Steel failure										
Characteristic resistance	N <sub>Rk,s,fi,120</sub>	(kN)	0,1	0,2	1,0	2,6	4,8	7,5	10,8	
Pull-out failure										
Characteristic resistance	Ng - 54m	(kN)	1,5	2,4	3,2	5,0	7,2	10,1	13,2	
in concrete C20/25 to C50/60	N <sub>Fk.p,fi,120</sub>	(KIV)	1,0	۷,٦	ن,د	5,0	1,4	10,1	10,2	
Concrete cone failure			-							
Characteristic resistance in concrete C20/25 to C50/60	N <sup>0</sup> <sub>Rk,cfi,120</sub>	(kN)	1,5	4,0	5,9	8,2	14,4	25,2	39,7	
O	S <sub>cr.N</sub>	(m <b>m</b> )				h <sub>ef</sub>	ef			
Spacing	S <sub>min</sub>	(m <b>m</b> )	40	60	70	80	100	125	150	
	C <sub>CLN</sub>	(m m)				2 x		,		
Edge distance		(mm)	C <sub>min</sub> = 2	2 x h <sub>ef</sub> ,	for fire	exposi	ure fror	n more		
	C <sub>min</sub>	1	than or	<u>ne side</u>	C <sub>min</sub> ≥ 3	<u>300 mn</u>	<u>n</u>			
n absence of other national regulat $r_{M,fi} = 1,0$ is recommended.	ions the parti	ial safe	ty factor	for res	sistance	under	fire exp	osure		
cher High-Performance Anchor FH	II and FH II.	——— A4		-						
aracteristic tension load resistance								Annex 8		



R30, Fire resistance 30 minutes			FH II	FH II	FHII	FH II	FH II	FH II	FHI
·			10	12	15	18	24	28	32
Steel failure without lever arm			,						
Characteristic resistance	V <sub>Rks,fi,30</sub>	(kN)	0,3	2,0	3,2	4,8	<b>8,</b> 9	<b>13</b> ,9	20,0
Steel failure with lever arm									
Characteristic bending resistance	M <sup>0</sup> <sub>Bk.s.fi.30</sub>	(Nm)	0	2	4	7	19	37	64
R60, Fire resistance 60 minutes		_	FH II 10	FH II 12	FHII 15	FH II 18	FH II	FH II 28	FH I
Steel failure without lever arm									
Characteristic resistance	$V_{Rks,fi,60}$	(kN)	0,3	1,3	<b>2</b> ,3	<b>3</b> ,9	7,3	11,3	16,0
Steel failure with lever arm									
Characteristic bending resistance	M <sup>0</sup> <sub>Rk.s.fi.60</sub>	(Nm)	0	1	3	6	15	30	52
R90, Fire resistance 90 minutes			FH II	FH II	FHII 15	FH II 18	FH II 24	FH II 28	FH 32
Steel failure without lever arm							-		
Characteristic resistance	$V_{Rk,s,fi,90}$	(kN)	0,2	0,6	1,4	3,0	5,6	8,8	12,6
Steel failure with lever arm									
Characteristic bending resistance	M <sup>0</sup> <sub>Rksfi.90</sub>	(Nm)	0	1	2	5	12	23	40
R120, Fire resistance 120 minutes		•	FH II 10	FH II 12	FHII 15	FH II 18	FH II 24	FH II 28	FH 1
Steel failure without lever arm									
Characteristic resistance	V <sub>Rk,s,<b>i</b>,120</sub>	(kN)	0,1	0,2	1,0	2,6	4,8	7,5	10,8
Steel failure with lever arm									
Characteristic bending resistance	M <sup>0</sup> <sub>Bk.s.fi.120</sub>	(Nm)	0	0	1	4	10	20	34
Characteristic Delicing resistance	DR.S.II.Jay								

1,0 for FH II 10 and the relevant values of  $N^0_{Rk,c,fl}$  of Table 9 have to be considered in the design.

## Concrete edge failure

The characteristic resistence V<sup>0</sup><sub>Rk,c,fi</sub> in concrete C20/25 to C50/60 is determined by:

$$V_{Rk,c,fi}^0 = 0,25 \times V_{Rk,c}^0$$
 (R30, R60, R90)

$$V_{Rk,c,fi}^0 = 0,20 \times V_{Rk,c}^0$$
 (R120)

with  $m V^o_{Rk,c}$  as initial value of the characteristic resistance in cracked concrete C20/25


under normal temperature according to ETAG 001, Annex C, 5.2.3.4.

In absence of other national regulations the partial safety factor for resistance under fire exposure  $\gamma_{M,fi} = 1,0$  is recommended.


fischer High-Performance Anchor FH II and FH II A4 Annex 9 Characteristic shear load values under fire exposure according to TR 020




# Installation instruction for the fischer high performance anchor FH II 10 - FH II 32 and FH II 10 A4 - FH II 24 A4




Installation instruction FH II 10 - 32 S and FH II 10-24 S A4



Installation instruction FH II 10 - 18 SK and FH II 10-18 SK A4



Installation instruction FH II 10 - 32 B and FH II 10-24 B A4



Installation instruction FH II 10 - 24 H and FH II 10-24 H A4

fischer High-Performance Anchor FH II and FH II A4	
Installation instruction	Annex 10